DEVELOPMENT SUMMARY

SITE INFO			
ADDRESS	33 - 43 Marion Street, Parramatta, NSW 2150		
DP	LOT 10-14 - DP 976 + LOT 1 - DP 747666 + LOT A DP 349279		
SITE AREA	2376 sqm		
PROJECT SUMMARY			
RESIDENTIAL MIX	1 Bedroom Unit : 58 2 Bedroom Unit : 207 3 Bedroom Unit : 31 TOTAL UNITS : 296		
RETAIL AREA (sqm)	605 sqm (GFA)		
CAR PARKING	194 RESIDENTIAL CAR PARKING SPACES		
PARRAMATTA LEP 2023			
	CONTROLS	**PROPOSED**	
LAND USE	MU1 - Mixed-Use	MU1 - Mixed-Use	✓
BUILDING HEIGHT (m)	N/A	128.05	
FLOOR SPACE RATIO	N/A	11.33:1	
GROSS FLOOR AREA (sqm)	N/A	26,925	
PARRAMATTA DCP 2023			
	CONTROLS	**PROPOSED**	**COMPLIANCE**
DWELLING MIX	Developments that proposed more than 20 dwellings are to provide a mix fo dwellings consistent with the following percentage mix : a. Studio : 5 - 10% b. 1 Bedroom : 10 - 30 % c. 2 Bedroom : 40 - 75 %, and d. 3+ Bedroom : 10 - 100 %	Proposed Dwelling Mix : 1 Bedroom : 58 (19.6%) 2 Bedroom : 207 (69.9%) 3 Bedroom : 31 (10.5%)	
COMMERCIAL FLOOR AREA	N/A		
SETBACK	**MARION ST SETBACK (NORTH BOUNDARY)** Street wall: 3m, 4 storey Above street wall: 6m **STATION ST SETBACK (EAST BOUNDARY)** Street wall: 6m with awning, 4 storey Above street wall: 9m **PEACE LANE SETBACK (SOUTH BOUNDARY)** Street wall: 4m **WEST BOUNDARY SETBACK** Street wall: 9m, 4 storey Above street wall: 12m	**MARION ST SETBACK (NORTH BOUNDARY)** GF to L3 = 3m L4 to L36 = 6m **STATION ST SETBACK (EAST BOUNDARY)** GF to L3 = 6m L4 to L36 = 9m **PEACE LANE SETBACK (SOUTH BOUNDARY)** GF to L3 = 4m L4 to L36 = 6m **WEST BOUNDARY SETBACK** GF to L3 = 9m L4 to L36 = 12m	
MIN. LANDSCAPE AREA	10% ~ 237.6 sqm	30% = 705.5 sqm	
CAR PARKING	**RESIDENTIAL CAR PARKING RATE** 0.3 space per 1 Bedroom dwelling = 0.3 x 58 = 17.0 spaces 0.7 space per 2 Bedroom dwelling = 0.7 x 207 = 145.0 spaces 1 space per 3 Bedroom dwelling = 1 x 31 = 31.0 spaces 0 visitor space per 1 dwellings = 0 spaces TOTAL REQUIRED RESIDENTIAL & VISITOR CAR PARKING SPACES **= 193 spaces** **COMMERCIAL CAR PARKING RATE** M=(GFA x SITEAREA) / (50 x Total Site GFA) TOTAL REQUIRED COMMERCIAL CAR PARKING SPACES **= 0 spaces** **TOTAL REQUIRED CAR PARKING SPACES = 193 spaces**	**RESIDENTIAL CAR PARKING** Resident car parking spaces : 194 spaces Residential visitor car parking spaces : 0 spaces TOTAL RESIDENTIAL CAR PARKING SPACES = 194 spaces **COMMERCIAL CAR PARKING** M=(GFA x SITEAREA) / (50 x Total Site GFA) TOTAL COMMERCIAL CAR PARKING SPACES = 0 spaces **TOTAL PROPOSED CAR PARKING SPACES = 194 spaces**	
BICYCLE PARKING	**RESIDENTIAL BICYCLE PARKING RATE** 1 space per dwelling (resident) = 1.0 x 296 = 296 spaces 1 spaces per 10 dwellings (visitor) = 0.1 x 296 = 29.6 spaces TOTAL REQUIRED RESIDENTIAL & VISITOR BICYCLE PARKING SPACES **= 326 spaces** **COMMERCIAL BICYCLE PARKING RATE** 1 space per 600sqm of commercial GFA = 642 / 600 = 1.07 spaces TOTAL REQUIRED COMMERCIAL BICYCLE PARKING SPACES **= 2 spaces** **TOTAL REQUIRED BICYCLE PARKINGSPACES = 328 spaces**	**RESIDENTIAL BICYCLE PARKING** Resident bicycle parking spaces : 296 spaces Resident visitor bicycle parking spaces : 32 spaces TOTAL REQUIRED RESIDENTIAL & VISITOR BICYCLE PARKING SPACES = 328 spaces **COMMERCIAL BICYCLE PARKING** Tenant bicycle parking spaces : 0 spaces Visitor bicycle parking spaces : 20 spaces TOTAL REQUIRED COMMERCIAL BICYCLE PARKING SPACES = 20 spaces **TOTAL PROPOSED BICYCLE PARKING SPACES = 348 spaces**	
MOTORCYCLE PARKING	**RESIDENTIAL MOTORCYCLE PARKING RATE** 1 space per 50 car spaces = 202 / 50 = 5 spaces **TOTAL REQUIRED MOTORCYCLE PARKING SPACES = 5 SPACES**	**RESIDENTIAL MOTORCYCLE PARKING** Residential motorcycle parking spaces : 5 spaces **COMMERCIAL MOTORCYCLE PARKING** Commercial motorcycle parking spaces : 0 spaces **TOTAL PROPOSED MOTORCYCLE PARKING SPACES = 5 spaces**	

APARTMENT DESIGN GUIDE			
	CONTROLS	**PROPOSED**	**COMPLIANCE**
3D. **COMMUNAL OPEN SPACE**	Communal open space has a minimum area equal to 25% of the site = 594 sqm	1,473 sqm	✓
3E. **DEEP SOIL ZONE**	6m minimum dimension, and equal to 7% of the site area = 166.32 sqm	657 sqm (27%)	✓
4A. **SOLAR AND DAYLIGHT ACCESS**	Living rooms and private open spaces of at least 70% of apartments in a building receive a minimum of 2 hours direct sunlight between 9 am and 3 pm at mid winter in the Sydney Metropolitan Area	88%	✓
4B. **NATURAL VENTILATION**	At least 60% of apartments are naturally cross ventilated in the first nine storeys of the building. Apartments at ten storeys or greater are deemed to be cross ventilated only if any enclosure of the balconies at these levels allows adequate natural ventilation and cannot be fully enclosed	61%	✓

ARCHITECTURAL LEGEND

	A
A	ALIGN
(A)	ACOUSTIC
AC	AIR CONDITIONING
AC*	AIR CONDITIONING WITH NON CLIMBABLE SHROUDS
ACC	ACCESSIBLE
ACP	AIR CONDITIONING CONTROL PANEL
ACS	ACCESS CONTROL SYSTEM
AD	ACCESS DECK
ADJ	ADJUSTABLE
ADP	ADAPTABLE
AH-01,.	ACCESS HATCH TYPE 01,02, ETC.
AHD	AUSTRALIAN HEIGHT DATUM
AJ	ARTICULATION JOINT
AL	ALUMINIUM
AMB	AMBULANT
AP	ACCESS PANEL
ASL	FIXED VERTICAL LADDER
ASP	ANTI-SLIP PLATE
AWF	APPLIED WALL FINISH
AWN	AWNING
	B
B	BATHROOM
BD-01,.	BEDROOM 1, BEDROOM 2, ETC.
BG	BOX GUTTER
BGS	BOOM GATE SYSTEM
BH	BULKHEAD
BJ	BUTT JOINT
BKP	BICYCLE PARKING
BKR	BICYCLE RACK
BKS	BICYCLE STORAGE
BL-01,.	BALUSTRADE-01, 02, ETC.
BLK	BLOCKWORK
BOL	BOLLARD
BO	BALCONY RAIN WATER OUTLET
BS	BALCONY SPRINKLER SLOT CAST INTO FULL DEPTH OF FOLD
BSH	BATHROOM SHELF
BSN	BASIN
BSP	BATH SPOUT
BST	BALLAST
BT	BENCHTOP
BTH-01.	BATH-01, 02, ETC.
BTP	BOTTLE TRAP
BTR	BOUNDARY TRAP
BWK-01.	BRICK TYPE 01, 02, ETC.
BY	BALCONY
BYW	BALCONY WINTER GARDEN
	C
CAP	CAPPING
CBC	CUBICLE SYSTEM
CBF	CONCRETE BROOM FINISH
CEA	CONCRETE EXPOSED AGGREGATE FINISH
CF	CRITICAL FACE
CFC	COMPRESSED FIBRE CEMENT
CFF	CONCRETE FLOAT FINISH
CGF	CONCRETE GROOVE FINISH
CH	CEILING HEIGHT
CHE	CHAMFERED EDGE
CHS	CIRCULAR HOLLOW SECTION
CI	CAST IN
CIS	CISTERN
CJ	CONTRUCTION JOINT
CKT	COOK TOP
CL	CENTRE LINE
CLD	CLADDING
CLK	CLOACK ROOM
CLNR	CLEANER STORE
CM	CONVEX MIRROR
CMR	CEMENT RENDER/ ACRYLIC
CNR	CORNER
COF	CONCRETE OFF-FORM FINISH
COL	COLUMN
COM	COMMERCIAL
COMS	COMMUNICATIONS SERVICES
CONC	CONCRETE FINISH
COS	CHECK ON SITE
CP	CAR PARK SPACE
CPC	CONCRETE PRECAST
CPD	CUPBOARD
CPL	COVER PLATE
CPS	CARPARK SUPPLY
CPT	CARPET
CPX	CAR PARK EXHAUST
CS	CEILING FINISH
CSF	CEMENTITIOUS SCREED FINISH
CSK	COUNTERSUNK
CSNK	CLEANERS SINK
CST	CONCRETE STEEL TROWEL FINISH
CTF	CERAMIC TILE FLOOR FINISH
CTW	CERAMIC TILE WALL FINISH
CU	CONDENSER UNIT
CVJ	COVED JUNCTION
CW	COLD WATER
CWB	CAR WASH BAY
CWS	COLD WATER SUPPLY
CY	COURTYARD
D	DINING
DD	DISH DRAIN
DDO	DISH DRAIN OUTLET
DG	DRIP GROOVE
DJ	DUMMY JOINT
DM	DOOR MAT
DP	DOWN PIPE
DPC	DAMP PROOF COURSE
DRB	PULLOUT BIN DRAWER
DRW	DRAWER
DRY	DRYER
DS	DOOR STOP
DW	DISHWASHER
	E
E	ENTRY
EA	EQUAL ANGLE
EDB	ELECTRICAL DISTRIBUTION BOARD
EFF	EPOXY FLOOR FINISH
EJ	EXPANSION JOINT
ELEC	ELECTRICAL SERVICE
EM	ENTRY MAT
EN	ENSUITE
EP	EDGE PROTECTION
EPO	EPOXY FLOOR FLINISH WITH COVERED CORNER
EX	EXISTING
EXH	EXHAUST
EXJ	EXPRESS JOINT
EXP	EXPOSED
	F
F	FIRE SERVICES
FB	FLUSH BUTTON (CISTERN)
FBV	FIRE BOOSTER VALVE
FC	FIBRE CEMENT
FCC	FIRE CONTROL CENTRE
FCL	FINISH CEILING LEVEL
FCR	FIRE CONTROL ROOM
FCU	FAN COIL UNIT (AC)
FEP	FIRE EGRESS PASSAGE
FES	FLOOR EDGE STRIP
FEX	FIRE EXTINGUISHER
FFL	FINISH FLOOR LEVEL
FG	FIXED GLASS
FGL	FINISHED GROUND LEVEL
FH	FIRE HYDRANT
FHB	FIRE HYDRANT BOOSTER
FHR	FIRE HOSE REEL
FIP	FIRE ALARM CONTROL PANEL
FLS	FLASHING
FMP	FIRE MIMIC PANEL
FN-01	FURNITURE TYPE 01, 02, ETC
FNC-01	FENCE TYPE 01, 02, ETC
FR	FIRE RATED
FRL	FIRE RESISTANCE LEVEL
FS-01,.	FIRE STAIR NO.1, 2, ETC
FSC	FIRE SPRINKLER CONTROL
FW	FLOOR WASTE
FX	FIXED
	G
GA-01	GREASE ARRESTOR NO.1, 2, ETC.
GB	GAS BAYONET
GBB	BULK GARBAGE ROOM
GBC	GARBAGE CHUTE
GBR	GARBAGE ROOM
GC	GLASS CLEAR
GD	GLASS, DECORATIVE
GDR	GRATED DRAIN
GE	GROOVED EDGE
GHR	GARBAGE HOLDING ROOM
GL-01,.	GLASS TYPE 01, 02, ETC.
GTR	GUTTER
GLR	MECHANICAL GRILLE
GM	GAS METER
GP	GLASS PANEL
GPO	GENERAL POWER OUTLET
GPT	GROSS POLLUTANT TRAP
GR	GRAB RAIL
GRL	GROUND LINE
GS	GLAZING SUITE
GT	GLASS, TRANSLUCENT
GX	GARBAGE EXHAUST
	H
H	HYDRAULIC SERVICES
HB	HEBEL
HC	HOSE COCK
HD	HANDLE
HDR	HAND DRYER
HIR	HIGH IMPACT RESISTANT
HK	HOOK
HMR	HIGH MOISTURE RESISTANCE
HP	HIGH POINT
HR-01,.	HANDRAIL-01, 02, ETC.
HRV	HEAVY RIGID VEHICLE
HWS	HOT WATER SERVICE
HWU	HOT WATER UNIT
	I
ID	INSIDE DIAMETER
IL	INVERT LEVEL
INA	INTEGRATED ASSEMBLY
INS	INSULATION
INT	INTERCOM
IO	INSPECTION OPENING
	J
J-01	JOINERY TYPE 01, 02, ETC.
JF-01	JOINERY FINISH 01, 02, ETC.
JP	JOINERY PULL
	K
K	KITCHEN
KB	KERB
KE	KITCHEN EXHAUST
	L
L	LIVING
LB	LETTER BOX
LBY	LOBBY
LCB	LIFT CALL BUTTON
LCL	LIFT CALL LANTERN
LF-01,.	LIFT-01, 02, ETC.
LG	LOWER GROUND
LM	PLASTIC LAMINATE
LP	LOW POINT
LRA	LOBBY RELIEF AIR
LSA	LOBBY SUPPLY AIR
LT	LAUNDRY TUB
LV	LOUVRES TYPE 01, 02, ETC
LY	LAUNDRY
	M
M	MECHANICAL SERVICES
MA	MEDIA ABOVE
MATV	MASTER ANTENNA TELEVISION SERVICE
MBP	MOTOR BIKE PARKING
MBX	MAIL BOX ASSEMBLY
MCP	PRESSED METAL CAPPING
MDR	METAL DECK ROOFING
MDSP	MULTI-USE DISPENSER UNIT
MGB	MOBILE GARBAGE BIN
MJ	MITRE JOINT
MOV	MICROWAVE OVEN
MR	MIRROR
MRR	MIRROR REVERSE
MRV	MEDIUM RIGID VEHICLE
MS	MASONRY WALL TILES
MSB	MAIN SWITCH BOARD SERVICES
MTR	METER
MV	MECHANICAL VENT
MVJ	MOVEMENT JOINT
	N
NGL	NATURAL GROUND LEVEL
NOM	NOMINAL
NB	NOTICE BOARD
	O
O	OPERABLE
OD	OVERHEAD DOOR
OF	OVER FLOW SLOT
OFS	OVER FLOW SPOUT
OP	OPERABLE
OSD	ON SITE DETENTION TANK
OSR	ON SITE RETENTION TANK
OV	OVEN
	P
P	PANTRY
PB	PLASTERBOARD
PC-01,.	POWDER COAT FINISH-01, 02, ETC.
PD	PIVOT DOOR
PDO	PLANTER DRAINAGE OUTLET
PF-01,.	PAINT FINISH-01, 02, ETC.
PFC	PARALLEL FLANGE CHANNEL
PG	PERGOLA
PL	PAINT LINE MARKING
PLB	PLANTER BOX
PLT	PLATFORM LIFT
PM	PELMET
PP_01	TRAFFIC ROAD MARKING PAINT
PP_02	SAFETY HAZARD STRIPS
PS	PIPIE SPACE
PRC	PRE CAST CONCRETE
PUP	PUSH PLATE
PV	PAVING
	R
R	ROBE
(R)	RECESSED
RA	RETURN AIR
RAS	ROOF ACCESS SAFTEY SYSTEM
RC	REINFORCED CONCRETE
RD	ROLLER DOOR
REP	RECESSED EDGE PULL
RES	RESIDENTIAL
RF	REFRIGERATOR
RFF	RESILIENT FLOOR FINISH
RH	RANGE HOOD
RHS	RECTANGULAR HOLLOW SECTION
RL	RELATIVE LEVEL TO AHD
RP-01,.	RAMP-01, 02, ETC.
RTL	RETAIL
RU	RECEPTABLE UNIT
RV	RELIEF VENT
RWH	RAIN WATER HEAD
RWO	RAINWATER OUTLET
RWT	RAINWATER TANK
RY	RECYCLING
	S
S	STORAGE
SA	SUPPLY AIR
SB	SPLASH BACK
SBM	STEEL BEAM
SBT	SEWER BOUNDRY TRAP
SC	STORAGE CAGE WITH GATE
SCN	SCREEN
SCOL	STEEL COLUMN
SCT	SHOWER CURTAIN
SCTR	SHOWER CURTAIN RAIL
SD	SLIDING DOOR
SDH	SOAP DISH HOLDER
SDO	SPOON DRAIN OUTLET
SDSP	SOAP DISPENSER
SEC	SECURITY SERVICES
SFF	STONE FLOOR FINISH
SFS	SHOWER FOLDING SEAT
SGN	SIGNAGE
SHC	SHAVING CABINET
SHP	SPEED HUMP
SHR	SHOWER
SHRR	SHOWER ROSE
SHS	SQUARE HOLLOW SECTION
SIM	SIMILAR
SJ	SAW JOINT
SK	SARKING
SKL-01,.	SKYLIGHT 01, 02, ETC.
SKT	SKIRTING
SLR	SEALANT
SMD	SMOKE DETECTOR
SN	SAFETY HAZARD
SNK	SINK
SO	STRUCTURAL OPENING
SOP	SET OUT POINT
SP	STAIR PRESSURISATION
SPR	STAIR PRESSURISATION RELIEF
SPT	SPOUT
SQE	SQUARE EDGE
(SR)	SEMI RECESSED
SS	STAINLESS STEEL
SSD	SUB-SURFACE DRAINAGE SYSTEM
SSL	STRUCTURAL SLAB LEVEL
SSN	SHOWER SCREEN
ST-01	STAIR NO.1, 2, ETC.
STL	STEEL
STN	STAIR NOSING
STP	SHOWER TAPSET
STY	STUDY
SV	SANITARY VENT
SW	STORM WATER
SWD	STORMWATER DRAIN
SWF	STONE WALL FINISH
SWP	STORMWATER PIT
	T
(T)	THERMAL
TCE	TERRACE
TD	TIMBER DECK
TDSP	TOWEL DISPENSER UNIT
TE	TOOLED EDGE
TF	TIMBER FLOOR FINISH
TFW	TRADE FLOOR WASTE
TGIS	TACTILE INDICATORS
TGSI	TACTILE GROUND SURFACE INDICATOR
TH	THRESHOLD
TND	TUNDISH
TOB	TOP OF BALUSTRADE
TOH	TOP OF HOB
TOS	TOP OF SCREEN
TOW	TOP OF WALL
TPH	TOPHAT
TPS	TAPSET
TR	TOWEL RAIL
TRA	TENANT RETURN AIR
TRH	TOILET ROLL HOLDER
TSA	TENANT SUPPLY AIR
TV	TIMBER VENEER
TYP.	TYPICAL
	U
U/G	UNDERGROUND
U/S	UNDERSIDE
UA	UNEQUAL ANGLE
UCT	UNDER CUT
UG	UPPER GROUND
UNO	UNLESS NOTED OTHERWISE
UR	URINAL
UT	UTILITY SPACE
	V
V	VOID
VIS	VISITOR
VN	VINYL
VP	VENT PIPE
	W
WC	WC
WC-A	WC-ACCESSIBLE
WC-F	WC- FEMALE
WC-M	WC- MALE
WC-U	WC- UNISEX
WIR	WALK IN ROBE
WM	WASHING MACHINE
WP	WEATHER PROOF
WPM-01,.	WATERPROOF MEMBRANE 01, 02, ETC.
WST	WHEEL STOP
WTM	WATERMETER
	X
XF-01	EXTERNAL WALL PAINT 01, 02, ETC.

GENERAL NOTES

© FUSE ARCHITECTURE.
•NO REPRODUCTION WITHOUT PERMISSION, UNLESS NOTED OTHERWISE.
•THIS DRAWING IS NOT FOR CONSTRUCTION.
•ALL DIMENSIONS AND LEVELS ARE TO BE CHECKED ON SITE PRIOR TO THE COMMENCEMENT OF WORK.
•SERVICE SPATIALS AND STRUCTURE ARE INDICATIVE ONLY. FINAL DESIGN TO BE DEVELOPED AND PROVIDED THERE IS NO CHANGE TO THE EXTERNAL ENVELOPE THIS WILL BE CONSIDERED CONSISTENT WITH THESE PLANS. DRAWINGS CANNOT BE RELIED UPON FOR THE BASIS OF MARKETING SALES OR CONSTRUCTION QUOTATION
•INFORM FUSE ARCHITECTURE OF ANY DISCREPANCIES FOR CLARIFICATION BEFORE PROCEEDING TO WORK.
•DRAWINGS NOT TO BE SCALED.
•USE ONLY FIGURED DIMENSIONS.
•REFER TO CONSULTANT DOCUMENTATION FOR FURTHER INFORMATION.

File: 2504_PARRAMATTA4
Print date and time: Friday, 5 December 2025 @ 12:31 PM

© FUSE ARCHITECTS.

CHANGE	DESCRIPTION

REVISION ID	AMENDMENT	DATE
P1	ISSUE FOR DRP 01	25/07/2025
P2	ISSUE FOR DRP 02	12/08/2025
A	ISSUE FOR SSDA SUBMISSION	4/12/2025

ARCHITECT
FUSE—ARCHITECTS
STUDIO 211-212
59 GREAT BUCKINGHAM STREET
REDFERN NSW 2016
MAIL@FUSEARCHITECTURE.COM.AU
PHONE 02 8278 7156
ABN 81 612 046 643
NOMINATED ARCHITECT RACHID ANDARY NSW ARB 8627

CLIENT
CN Marion Pty Ltd
L 2/111 Parramatta Rd
Concord NSW 2137

FOR APPROVAL

SITE ADDRESS
33-43 MARION STREET PARRAMATTANSW 2150

JOB NO
2504

CHECKED VC/AD
DRAWN KH
DATE APR 2025
SCALE @ A1 A3@50%

PROJECT STATUS
STATE SIGNIFICANT DESIGN APPLICATION

DRAWING TITLE
DEVELOPMENT SUMMARY

SHEET NO. SSDA 002
REVISION. A