ARCHITECTURAL LEGEND

	A
AC	AIR CONDITIONING
ACC	ACCESSIBLE
ADP	ADAPTABLE
AH	AFFORDABLE HOUSING
AHD	AUSTRALIAN HEIGHT DATUM
AL	ALUMINIUM
AMB	AMBULANT
AP	ACCESS PANEL
AWN	AWNING
	B
B	BATHROOM
BD	BEDROOM 1, BEDROOM 2, ETC.
BG	BOX GUTTER
BGS	BOOM GATE SYSTEM
BH	BULKHEAD
BKP	BICYCLE PARKING
BKR	BICYCLE RACK
BKS	BICYCLE STORAGE
BL	BALUSTRADE
BLK	BLOCKWORK
BOL	BOLLARD
BSN	BASIN
BT	BENCHTOP
BTH	BATH
BTR	BOUNDARY TRAP
BWK	BRICK (FACE BRICK)
BWU	BRICK (GLAZED FEATURE BRICK)
BY	BALCONY
	C
C	COMMERCIAL
CFC	COMPRESSED FIBRE CEMENT
CLD	CLADDING
CLNR	CLEANER STORE
CMR	CEMENT RENDER/ ACRYLIC
COF	CONCRETE OFF-FORM FINISH
COM	COMMERCIAL
COMS	COMMUNICATIONS SERVICES
CON	CONCRETE FINISH
COS	COMMUNAL OPEN SPACE
CP	CAR PARK SPACE
CPC	CONCRETE PRECAST
CPE	CAR PARK EXHAUST
CPS	CARPARK SUPPLY
CU	CONDENSER UNIT
CUF	CONDENSER UNIT FARM
CW	COLD WATER
CWB	CAR WASH BAY
CWS	COLD WATER SUPPLY
CY	COURTYARD
	D
D	DINING
DP	DOWN PIPE
	E
E	ENTRY
EDB	ELECTRICAL DISTRIBUTION BOARD
ELEC	ELECTRICAL SERVICE
EM	ENTRY MAT
EN	ENSUITE
(EX)	EXISTING
EXH	EXHAUST

	F
FBV	FIRE BOOSTER VALVE
FC	FIBRE CEMENT
FCC	FIRE CONTROL CENTRE
FFL	FINISH FLOOR LEVEL
FG	FIXED GLASS
FGL	FINISHED GROUND LEVEL
FH	FIRE HYDRANT
FHB	FIRE HYDRANT BOOSTER
FHR	FIRE HOSE REEL
FIP	FIRE ALARM CONTROL PANEL
FNC	FENCE
FRL	FIRE RESISTANCE LEVEL
FS_01	FIRE STAIR NO.1, 2, ETC
	G
GA_01	GREASE ARRESTOR NO.1, 2, ETC.
GBC	GARBAGE CHUTE
GBR	GARBAGE ROOM
GC	GLASS CLEAR
GD	GLASS, DECORATIVE
GDR	GRATED DRAIN
GHR	GARBAGE HOLDING ROOM
GL	GLASS TYPE
GRL	GROUND LINE
	H
H	HYDRAULIC SERVICES
H/L	HIGH LEVEL WINDOWS
HR	HANDRAIL
HRV	HEAVY RIGID VEHICLE
HWS	HOT WATER SERVICE
HWU	HOT WATER UNIT
	I
IL	INVERT LEVEL
INT	INTERCOM
	J
J_01	JOINERY TYPE 01, 02, ETC.
	K
K	KITCHEN
KB	KERB
KE	KITCHEN EXHAUST
	L
L	LIVING
LB	LETTER BOX
LBY	LOBBY
LG	LOWER GROUND
LV	LOUVRES
LY	LAUNDRY
	M
M	MECHANICAL SERVICES
MBP	MOTOR BIKE PARKING
MBX	MAIL BOX ASSEMBLY
MCP	PRESSED METAL CAPPING
MDR	METAL DECK ROOFING
MR	MIRROR
MRV	MEDIUM RIGID VEHICLE
MSB	MAIN SWITCH BOARD SERVICES
MTR	METER
	N
NC	NAPPY CHANGE
NGL	NATURAL GROUND LEVEL
	O
OD	OVERHEAD DOOR
OSD	ON SITE DETENTION TANK
OSR	ON SITE RETENTION TANK

	P
PC_01	POWDER COAT FINISH
PLB	PLANTER BOX
PLT	PLATFORM LIFT
PRC	PRE CAST CONCRETE
PV	PHOTOVOLTAIC PANEL
PV_01	CONCRETE FOOTPATH
PV_02	STONE UNIT PAVING
PV-03	ASPHALT PAVEMENT
PV_04	STABILISED CRUSHED AGGREGRATE
PV_05	FEATURE PAVEMENT BANDING
PV_06	ROOF PEBBLES
	R
R	ROBE
RD	ROLLER DOOR
RES	RESIDENTIAL
RTL	RETAIL
RY	RECYCLING
RWH	RAIN WATER HEAD
RWT	RAINWATER TANK
	S
S	STORAGE
SBT	SEWER BOUNDRY TRAP
SC	STORAGE CAGE WITH GATE
SCN	SCREEN
SCOL	STEEL COLUMN
SGN	SIGNAGE
SHP	SPEED HUMP
SHR	SHOWER
SKL	SKYLIGHT
SP	STAIR PRESSURISATION
SS	STAINLESS STEEL
ST_01	STAIR NO.1, 2, ETC.
STY	STUDY
SUBS	SUBSTATION
SV	SERVICE
SW	STORM WATER
	T
TCE	TERRACE
TD	TIMBER DECK
TF	TIMBER FLOOR
TGSI	TACTILE INDICATORS
TOH	TOP OF HOB
TOS	TOP OF SCREEN
TOW	TOP OF WALL
TYP.	TYPICAL
	U
UG	UPPER GROUND
UR	URINAL
UT	UTILITY SPACE
	V
V	VOID
VIS	VISITOR
	W
WC	WC
WC_A	WC- ACCESSIBLE
WC_F	WC- FEMALE
WC_M	WC- MALE
WC_U	WC- UNISEX
WPM	WATERPROOF MEMBRANE SYSTEM
WST	WHEEL STOP
WTM	WATERMETER

DEVELOPMENT SUMMARY

SITE INFO				
ADDRESS	8-10 Levuka Street, Cabramatta NSW 2166			
DP	24/DP7111, 23/DP7111			
SITE AREA	2,024 sqm			
PROJECT SUMMARY				
RESIDENTIAL MIX	1 Bedroom Unit : 3 2 Bedroom Unit : 18 3 Bedroom Unit : 10 TOTAL UNITS : 31			
CHILDCARE AREA (sqm)	598.00			
CAR PARKING	62 CAR PARKING SPACES; consisting of 10 Parent Parking Spaces,16 Staff Parking space, 1 Residential Visitor Parking Spaces, and 35 Residential Parking Spaces			
SEPP (HOUSING) 2021				
	CONTROLS	**CONTROLS + 30% INFILL AFFORDABLE HOUSING**	**PROPOSED**	
LAND USE	R3 - Medium Density Residential	R3 - Medium Density Residential	R3 - Medium Density Residential	
BUILDING HEIGHT (m)	17.50	22.75	22.95	
FLOOR SPACE RATIO	1.50	1.95	1.83	
GROSS FLOOR AREA (sqm)	3,036.00	3,947	3,721.00	
ACECQA + CHILDCARE PLANNING GUIDELINES				
	CONTROLS		**PROPOSED**	**COMPLIANCE**
EDUCATOR TO CHILD RATIO	0 - 24 months = 24 - 36 months = 36 months+ = 4yrs+ =	1:4 1:5 1:10 1:15	0 - 24 months = 24 - 36 months = 36 months + = TOTAL =	16 children | 4 educators 40 children | 8 educators 40 children | 4 educators | 16 staff ✓
PLAY SPACES	**Unencumbered Outdoor Play Space** Ground Floor (0-24 mths + 24-36 mths + 3-6yrs) =	7sqm / child	**Unencumbered Outdoor Play Space** Ground Floor (0-24 mths + 24-36 mths + 3-6yrs) =	674 sqm or 7.02 sqm / child
	Unencumbered Indoor Play Space 0-24 months = 24-36 months = 3-5 years =	3.25sqm / child 3.25sqm / child 3.25sqm / child	**Unencumbered Indoor Play Space** 0-24 months - 16 infants: 24-36 months - 40 children: 3-5 years - 40 children:	55 sqm or 3.44 sqm / child 138sqm or 3.45 sqm / child 136 sqm or 3.4 sqm / child ✓
STORAGE	Outdoor Space= Indoor Space 0-24 months = 24-36 months = 3-5 years =	0.3m3 / child 0.2m3 / child 0.2m3 / child 0.2m3 / child	Outdoor Space = Indoor Space 0-24 months - 16 infants = 24-36 months - 40 children = 3-5 years - 40 children =	29.53 m3 0.31 m3/child care place 7m3 - 0.44 m3/child 23m3 - 0.58 m3/child 10m3 - 0.25 m3/child ✓
FAIRFIELD CITY WIDE DCP 2024				
	CONTROLS	**CONTROLS + 30% INFILL AFFORDABLE HOUSING**	**PROPOSED**	**COMPLIANCE**
DWELLING MIX	There is no minimum requirement for 1, 2 or 3 + bedroom dwellings on the R3 Medium Density Residential land. a. Studio : b. 1 Bedroom : c. 2 Bedroom : d. 3+ Bedroom :		Proposed Dwelling Mix : Non-Affordable: 1 Bedroom : 2 (6%) 2 Bedroom : 14 (45%) 3 Bedroom : 8 (26%) Total : 24 (77%)	 Affordable: 1 Bedroom : 1 (3%) 2 Bedroom : 4 (13%) 3 Bedroom : 2 (6%) Total : 7 (23%) ✓
CHILDCARE FLOOR AREA	0% = 0 sqm		571 sqm	
SETBACK	FRONT SETBACK		FRONT SETBACK	
LEVUKA STREET	Street wall: 6m, 6 storey REAR SETBACK Street wall: 6m, 4 storey Above street wall: 9m SIDE SETBACK Street wall: 6m, 4 storey Above street wall: 9m		GF to L5 = 6m REAR SETBACK GF to L3 = 9m L4 to L5 = 9m SIDE SETBACK GF to L3 = 6m L4 to L5 = 9m	✓
MIN. LANDSCAPE AREA	10% ~ 202.4 sqm	SEPP (HOUSING) 2021 NSW 30% ~ 607.2 sqm	30% = 608sqm	
CAR PARKING	**RESIDENTIAL CAR PARKING RATE** SEPP Infill Affordable Housing Parking Rates **= 4.4 spaces** 0.4 space per 1B: 1/0.4 = 0.4 space 0.5 space per 2B: 4/0.5 = 2 spaces 1 space per 3B: 2/ = 2 spaces SEPP Infill Non-Affordable Housing Parking Rates **= 27 spaces** 0.5 space per 1B: 2/0.5 = 1 spaces 1 space per 2B: 14/1 = 14 spaces 1.5 spaces per 3B: 8/1.5 = 12 spaces RESIDENTIAL TOTAL **= 31.4 spaces** VISITOR • 0 spaces required (per Kogarah Investments NSWLEC 1048) CARWASH • 1 carwash space per 60 dwellings: 31/60 = 0.52 space TOTAL REQUIRED PARKING SPACES **= 31.92 spaces** **CHILDCARE CAR PARKING RATE** 1 space per 10 children = 10 spaces 1 space per 1 staff = 16 spaces Accessible parking space = 1 space (at least 1,shared with parent) TOTAL PARKING SPACE = 26 spaces **TOTAL REQUIRED PARKING SPACES = 57.92 spaces**		**RESIDENTIAL CAR PARKING** RESIDENTIAL TOTAL **= 35 spaces** CARWASH • 1 carwash space per 60 dwellings: 1 space TOTAL PROPOSED PARKING SPACES **= 36 spaces** **CHILDCARE CAR PARKING** Parent car parking spaces (inc. 1 ACC) = 10 spaces Staff car parking spaces = 16 spaces TOTAL CHILDCARE CAR PARKING SPACES = 26 spaces **TOTAL PROPOSED CAR PARKING SPACES = 62 spaces**	✓
BICYCLE PARKING	**RESIDENTIAL BICYCLE PARKING RATE** 1 space per dwelling (resident) = 1.0 x 31 = 31 spaces 1 spaces per 10 dwellings (visitor) = 0.1 x 31 = 3.1 spaces **TOTAL REQUIRED BICYCLE PARKING SPACES** **= 34.1 spaces**		**RESIDENTIAL BICYCLE PARKING** Resident bicycle parking spaces : 35 spaces Resident visitor bicycle parking spaces : 4 spaces **TOTAL PROPOSED BICYCLE PARKING SPACES** **= 39 spaces**	✓
MOTORCYCLE PARKING	**RESIDENTIAL MOTORCYCLE PARKING RATE** 1 space per 15 car spaces = 34.1 / 15 = 2.3 spaces		**RESIDENTIAL MOTORCYCLE PARKING** Residential motorcycle parking spaces : 3 spaces	✓
APARTMENT DESIGN GUIDE				
	CONTROLS		**PROPOSED**	**COMPLIANCE**
3D. COMMUNAL OPEN SPACE	Communal open space has a minimum area equal to 25% of the site = 506 sqm		510 sqm	✓
3E. DEEP SOIL ZONE	6m minimum dimension, and equal to 7% of the site area = 141.68 sqm		380 sqm	✓
4A. SOLAR AND DAYLIGHT ACCESS	Living rooms and private open spaces of at least 70% of apartments in a building receive a minimum of 2 hours direct sunlight between 9 am and 3 pm at mid winter in the Sydney Metropolitan Area		84%	✓
4B. NATURAL VENTILATION	At least 60% of apartments are naturally cross ventilated in the first nine storeys of the building. Apartments at ten storeys or greater are deemed to be cross ventilated only if any enclosure of the balconies at these levels allows adequate natural ventilation and cannot be fully enclosed		65%	✓

GENERAL NOTES
© FUSE ARCHITECTS.
•NO REPRODUCTION WITHOUT PERMISSION
UNLESS NOTED OTHERWISE.
•THIS DRAWING IS NOT FOR CONSTRUCTION.
•ALL DIMENSIONS AND LEVELS ARE TO BE CHECKED ON SITE
PRIOR TO THE COMMENCEMENT OF WORK.
•SERVICES SPATIALS + STRUCTURE ARE INDICATIVE ONLY; FINAL DESIGN TO BE DEVELOPED AND PROVIDED THERE IS NO CHANGE TO THE EXTERNAL ENVELOPE/COMPLIANCE THIS WILL BE CONSIDERED CONSISTENT WITH THESE PLANS.
•INFORM FUSE ARCHITECTURE OF ANY •DISCREPANCIES FOR CLARIFICATION BEFORE PROCEEDING WITH WORK.
•DRAWINGS ARE NOT TO BE SCALED.
•USE ONLY FIGURED DIMENSIONS.
•REFER TO CONSULTANT DOCUMENTATION FOR FURTHER INFORMATION.
File: 2509_CABRAMATTA1
Print date and time: Wednesday, 15 July 2026 @ 7:58 PM
© FUSE ARCHITECTS.

REVISION ID	AMENDMENT	DATE
P4	ISSUE FOR COORDINATION	26/09/2025
P5	ISSUE FOR COORDINATION	3/10/2025
A	DEVELOPMENT APPLICATION	27/10/2025
D	DEVELOPMENT APPLICATION	29/05/2026
E	DEVELOPMENT APPLICATION	15/07/2026

ARCHITECT
FUSE—ARCHITECTS
STUDIO 212
59 GREAT BUCKINGHAM STREET
REDFERN NSW 2016
MAIL@FUSEARCHITECTURE.COM.AU
PHONE 02 8278 7156
ABN 81 612 046 643
NOMINATED ARCHITECT RACHID ANDARY NSW ARB 8627

CLIENT
CHEGO
Levuka Developments
info@chego.com.au
0424 305 085

SITE ADDRESS
8 & 10 LEVUKA STREET, CABRAMATTA NSW 2166 AUSTRALIA

JOB NO
2509

CHECKED VC/GA
DRAWN EQ/KT
DATE JUN 2025
SCALE @ A1 A3@50%

PROJECT STATUS
DEVELOPMENT APPLICATION

DRAWING TITLE
DEVELOPMENT SUMMARY

SHEET NO. DA 002
REVISION. E